



ADDENDUM NO. 1

DATE: May 22, 2017
PROJECT NAME: Warson Woods * 2017
Street Program
PROJECT NUMBER: 160055-0001

TO: All Bidding Contractors

CC: Mike Dell'Orco - City of Warson Woods
KdG Design Team
File

This Addendum forms a part of the Contract Documents and modifies previously issued Documents. Acknowledge receipt of this Addendum on the Bid Form. Failure to do so may subject Bidder to disqualification.

SPECIFICATIONS

Description of Work

1. In WARD 1 the following addition:
 - Andrew Drive at Warson Woods Drive: Trench Drain, replace the concrete seat ledge on the east side of the trench drain (26 feet), replace one section of grate seat (4 feet) and ensure all grates are correctly bolted down. Trench Drain shall be cleaned of all debris after construction.

Unit Price Extension Sheet

1. A new Unit Price Extension Sheet has added the Trench Drain Repair. It is attached to this addendum and shall be used on the project.

End of Document

AJG/kmn

K:\Warson Woods\MO\160055 Warson Woods 2016 Street Pgm\11 Construction\04 Addendums\551_ADD1-Writeup-2017-05-22.docx

UNIT PRICE EXTENSION SHEET
STREET IMPROVEMENTS AND PAVEMENT REPLACEMENT
INITIAL WORK 2017

The base bid shall be the total of the extended prices bid for each of the separate items in the initial work in 2017. Unit prices shall be utilized in determining the amount to be added or deducted from the base bid for significant additions or deletions to the work shown on the plans and included in written change orders. Quantities are not guaranteed but they shall not vary from estimates by an unreasonable amount.

NOTES:

1. The following factors were used in the quantity estimates:
One (1) square yard of crushed stone six inches (6") deep = .32 tons.
2. Pay items correspond to St. Louis County Standard Specifications for Highway Construction Items, except as modified by these Specifications.

CONTRACTOR NAME _____

<u>ITEM</u>	<u>PAY ITEM</u>	<u>ESTIMATED QUANTITY</u>	<u>UNIT</u>	<u>UNIT PRICE</u>	<u>EXTENDED PRICE</u>
A.	Pavement removal and P.C. concrete pavement replacement.	108	SY		
B.	Pavement Removal and High Early strength Concrete Replacement	40	SY		
C.	Crushed stone base	48	Tons		
D.	Seal concrete pavement	148	SY		
E.	Hot Poured Crack Sealant	2400	L.F.		
F.	Trench Drain Repair	1	LS		
G.	Mobilization	1	LS		
TOTAL PRICE					

Bid Alternate No. 1					
X.	Asphalt Pavement. 2 inch mill and overlay	275	SY		
TOTAL BID ALTERNATE NO. 1 PRICE					

Note: Unit prices will be used to add or delete portions of this work where Owner or Engineer deems necessary. Small or large amounts may be added or removed (individual PCC slabs, or individual locations of sidewalk removal/replacement) depending on total budget for project.